BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Satellite Town Sub Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
BBMP, Bangalore

Approved Tender SCHEDULE –'B'

Name of Work:-Improvements of drains and asphalting to 22nd cross in Judicial Layout in ward no 04					
Sl.No	Description of work	Unit	Approved Qty	Rate quoted by the contractor	
				Rate	Rate in words
1	Removing B.S slab of drain and stacking	sqm	1411.00	58.32	Rupees fifty eight and paise thirty two only
2	Refixing stone slabs of drains and pointing in CM(1:3)	Sqm	1411.00	75.60	Rupees seventy five and paise sixty only
3	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete **do 7.5 cms** thick	sqm	405.00	639.36	Rupees six hundred thirty nine and paise thirty six only
4	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no138,PWD SR 2014-15)	Cum	1369.50	75.60	Rupees seventy five amd paise sixty only
5	KSRRB 500-2. Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	1662.50	3.02	Rupees three and paise two only
6	KSRRB M400-17: Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification: 406 (PWD SR 2014-15 P.N.154 It 20.18)	**Cum**	440.44	1438.56	Rupees one thousand four hundred thirty eight and paise fifty six only

7	KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM,WMM including cleaning of road surfase and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH SpecificationsNo502 (ITEMNO21.6,Page no157,PWD SR 2014-15)	Sqm	2625.00	35.21	Rupees thirty five and twenty one only
8	KSRRB M500-18.Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler, transporting the hot mix to work site.laying with a paver finisher to the required grade,levell and alignment, rolling withs mooth wheeled,vibratoryandtandemrollers to achievethe desired compactiona sperMORTHSpecificationclauseno508completeinallrespectscompleteas perspecifications.using40-60 TPH capacity HMP with mechanical pavour grading -II (25-30mm) with 5% CRMB 55 grade (Itemno 21.21.5 Pageno 160 2014-15)	Cum	78.75	10871.28	Rupees ten thousand eight hundred seventy one and paise twenty eight only
9	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum. KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no 130, PWD SR 2014-15)	Cum	1369.50	68.04	Rupees sixty eight and paise four only

Signature of the contractor

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL BBMP, Bangalore

Executive Engineer
Yelahanka Division
BBMP, Bangalore